



15-169-00642-00-01

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) STATE CORPORATION COMMISSION
500 Insurance Bldg. 212 N. Main St.
WICHITA, KANSAS 67202

RECEIVED
MAR 26 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

March 12, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, Mc Pherson, Kansas 67460

Lease Name: Cravons Well No. 1

Location: NW SE SW Sec. 20 Twp. 14 Rge. 2 (B) (W) X

County: Saline Total Depth 3452' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3250' and cement with 5 sacks.

Fill hole with mud to 240'. Set rock bridge from 240' to 230' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Albert J. Sorensen
Conservation Division Agent