



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

August 18, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1963

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Walter J. Nelson

Complete Address: 2080 Edwards, Salina, Kansas

Lease Name: Roesner Well No. 1

Location: NE NE SW Sec. 9 Twp. 14 Rge. 2 (E) (W) X

County Saline Total Depth 3250' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push plug to 3110'. Fill hole with sand to 3100' and cement
with 5 sacks. Fill hole with mud to 170'. Set rock bridge
from 170' to 160' and cement hole to base of cellar with
2 1/2 yards ready mix cement.

Very truly yours,

William J. Loman
 Conservation Division Agent