



15-169-30009-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 1, 1965

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 7 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Walter J. Nelson

Complete Address: 2072 Marc, Salina, Kansas

Lease Name: Cravens Well No. 2

Location: SW SE Sec. 9 Twp. 14 Rge. 2 (X) (W) X

County Saline Total Depth 3170' Oil Well X


Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Hole had been plugged back (cement) to 2650'. Cement was not drilled out.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent