



15-169-00966-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

August 18, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Fred Shaffer, Jr.

Complete Address: 404 Wolcott Bldg., Hutchinson, Kansas 67501

Lease Name: Deiter Well No. 1

Location: NE SE SE Sec. 8 Twp. 14 Rge. 2 (S) (W) X

County: Saline Total Depth 3197' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clark was instructed to plug the well as follows:

Fill hole with sand to 3175' and cement with 3 sacks cement.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent