

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-171-20,354 -00-00

LEASE NAME Geeseka

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3960 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 28 TWP. 19 RGE. 33 ~~XXXX~~ (W)

COUNTY Scott

LEASE OPERATOR Lebsack Oil Production, Inc.

ADDRESS P.O. Box 489, Hays, KS 67601

PHONE# (913) 625-3046 OPERATORS LICENSE NO. 5210

Date Well Completed 2-15-87

Character of Well D&A

Plugging Commenced 2-14-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-15-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1, State plugger Richard Lacey

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Sent to operator for completion Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	394	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump heavy mud to 2225'-2025', 50 sacks; pump heavy mud to 1300'-980', 80 sacks; pump heavy mud to 425'-225', 50 sacks; pump heavy mud to 40' to solid bridge, 10 sacks; 15 sacks in the rathole; all cement 60/40 posmix, 6% gel, 3% ca. cl.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

FEB 25 1987
 02-05-87
 CONSERVATION DIVISION
 WICHITA, KANSAS

Jack K. Wharton, Secy/Treas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
 Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

Subscribed and sworn to before me this 24th day of February, 19 87

Clarice M. Mize
 Clarice M. Mize Notary Public
 Commission Expires: November 28, 1988

