

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-171-20,340-00-00

LEASE NAME Smith "G"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 27 TWP. 19S RGE. 33 000 or (W)

COUNTY Scott

LEASE OPERATOR American Energies Corporation

ADDRESS 575 Fourth Financial Corporation

PHONE# (316) 263-5785 OPERATORS LICENSE NO. 5399

Date Well Completed 8-21-86

Character of Well D & A

Plugging Commenced 8-21-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-21-86

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1 Dan Goodrow

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Sent to operator to complete. Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	395'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump hvy mud to 2190'. 1st plug from 2190' to 1990' w/50 sx; 2nd plug from 1450' to 1050' w/100 sx; 3rd plug from 425' to 225' w/50 sx; filled w/heavy mud 225' to 40'. Solid bridge at 40'. 4th plug from 40' to surface w/10 sx. 10 sx in rathole. All cement 60/40 posmix 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422


Address 801 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Abercrombie Drilling, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jared P. Pate

(Address) 801 Union Center, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 4th day of September, 1986

Judy L. Heitkotter
 Judy L. Heitkotter, Notary Public

Expires: 6-24-89.

SEP 8
 09-08-86