


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-171-20025-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Scott County, Sec. 26 Twp. 19 Rge. 33 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines C NW NE
Lease Owner Maurice L. Brown
Lease Name Smith A#12 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/19/76 _____ 19____
Plugging completed 1/23/76 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced YES

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4754 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	364	none
				4 1/2"	4754	1479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4754', ran sand to 4625' and ran 3 sacks cement.
Loaded hole with water, shot pipe at 3494', 2000', 1747', 1490',
pulled 45 joints. Pumped 5 sacks hulls, 70 sacks cement, 8 sacks
gel and 60 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1976

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

DRILLER'S LOG

15-171-20025-00-00

COMPANY
CONTRACTOR
FARM
LOCATION

YUCCA PETROLEUM COMPANY
LEBEN DRILLING, INC.
SMITH #12
C NW NE SECTION 26-19S-33W
SCOTT COUNTY, KANSAS

COMMENCED
COMPLETED

9-20-69
10-5-69

0	40	Clay, Sand
40	364	Sand, Shale
364	1881	Shale
1881	2184	Shale, Red Bod
2184	2202	Anhydrite
2202	2355	Shale, Red Bod
2355	2530	Shale
2530	3225	Shale, Lime
3225	4756	Lime
	<u>4756</u>	<u>LTD</u>

8 5/8" 20# new surface casing set @ 364' cemented with 270 sacks common 3% cc


I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith #12 Well, located C NW NE of Section 26, Township 19 South, Range 33 West of Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 10th day of October, 1969.

Ulanda Nichols
Ulanda Nichols



RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1969
CONSERVATION DIVISION
Wichita, Kansas