


15-171-20026-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Scott County, Sec. 26 Twp. 19S Rge. 33 ~~XXX~~ (W)
Location as "NE/CNW&SW" or footage from lines. C SE NE
Lease Owner Yucca Petroleum Co.
Lease Name Smith Well No. 13
Office Address P. O. Box 2585, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1969
Application for plugging filed November 1 1969
Application for plugging approved November 1 1969
Plugging commenced November 1 1969
Plugging completed November 1 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	354'	None

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted Halliburton light cement plugs through open ended
drill pipe as follows:

- 20 sx (4515-4600')
- 80 sx (650 -1000')
- 20 sx (300 -390')
- 10 sx (0 - 40')

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF TEXAS, COUNTY OF POTTER, ss.
Eddie C. Podzemny, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eddie C. Podzemny, Jr.
P. O. Box 2585, Amarillo, Texas 79105
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of November, 1969

Karen Sue Becker
Notary Public.

My commission expires 6-1-71

DRILLER'S LOG

COMPANY: YUCCA PETROLEUM
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SMITH # 13
 LOCATION: 150'W-C SE NE SECTION 26-19S-33W
 SCOTT COUNTY, KANSAS
 COMMENCED: 10-20-69
 COMPLETED: 11-1-69

0	190	Clay & Sand
190	354	Shale & Post Rock
354	1525	Shale
1525	1905	Shale & Red Bed
1905	2176	Shale
2176	2194	Anhydrite
2194	2380	Shale
2380	2575	Lime
2575	2915	Shale & Lime
2915	3045	Lime
3045	3195	Lime & Shale
3195	3505	Lime
3505	3640	Lime & Shale
3640	4710	Lime
	<u>4710</u>	<u>RTD D&A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 22 1970
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" new 20# surface casing wet @ 354' cemented with 270 sacks
 Common 2% C.C. 1/2# Flosal per sack.

I, James R. Rodgers, do hereby certify that the above and foregoing
 is a true and correct copy of the log of the Smith #13 Well, located
 150' W - C SE NE Section 26, Township 19 South, Range 33 West, Scott
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

James R. Rodgers
 James R. Rodgers

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 5th day of December, 1969.

Helen L. Lindenmuth
 Helen L. Lindenmuth

My Commission Expires:
 November 13, 1974

15-171-20026-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1969
CONSERVATION DIVISION
Wichita, Kansas



YUCCA petroleum co.

300 FIRST NATIONAL BANK BUILDING • TELEPHONE 806 376-5431 • P.O. BOX 2585 • AMARILLO, TEXAS 79105

November 6, 1969

State Corporation Commission
Conservation Division
5th Floor - Insurance Building
212 N. Market
Wichita, Kansas 67202

Attention: Mr. S. S. Greider

Re: Smith No. 12
C NW NE Sec. 26-19S-33W
Scott County, Kansas

Gentlemen:

Thank you for your letter of October 31, 1969, granting Yucca Petroleum Co. permission to temporarily abandon the Smith No. 12 well.

The long string of casing was set at 4754 feet. We ran 144 joints of 4-1/2" O.D. K-55, 9.5# casing and cemented with 200 sacks of 50-50 Pozmix cement, 18% salt, 3/4% CFR-2, 1/4# flocele per sack, 2 plug-mithod.

I hope this information is sufficient for your records.

Very truly yours,

YUCCA PETROLEUM CO.

Eddie C. Podzemny, Jr.

Eddie C. Podzemny, Jr.
Production Clerk

ECP:lc

File