

15-171-20009-00-00

STATE OF KANSAS


STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Scott County, Sec. 26 Twp. 19 Rge. 33W (W)
Location as "NE/CNW/SE/SW" or footage from lines C NW NW
Lease Owner Yucca Petroleum Company
Lease Name Smith #2 Well No.
Office Address Box 2585, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-31-68 19 68
Application for plugging filed 8-31-68 19 68
Application for plugging approved 8-31-68 19 68
Plugging commenced 8-31-68 19 68
Plugging completed 8-31-68 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Pfannenstiel
Producing formation Depth to top Bottom Total Depth of Well 4868 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 8 5/8", 384.07, none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 50 sacks 50/50 Posmix @ 4600 thru pipe
Spotted 100 sacks @ 1000' thru pipe Bridged @ 40' with 1/2 Hulls
Plug 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lulu Kite

(Address)
Ulanda Nichols
Notary Public.

SUBSCRIBED AND SWORN TO before me this 31st day of August 19 68
My commission expires April 1, 1971

15-171-20009-00-00

DRILLER'S LOG

COMPANY Yucca Petroleum Company
CONTRACTOR Leben Drilling, Inc.
FARM Smith #2
LOCATION C NW NW Section 26-19S-33W
Scott County, Kansas
COMMENCED 8-17-68
COMPLETED 8-31-68

0	70	Gravel, Sand
70	195	Sand, Gravel
195	393	Shale
393	1515	Shale, Sand
1515	2190	Shale, Red Bed
2190	2210	Anhydrite
2210	2380	Shale, Shells
2380	2465	Shale, Lime
2465	3075	Lime, Shale
3075	3200	Lime
3200	3315	Lime, Shale
3315	4554	Lime
4554	4630	Lime, Chert, Sand
4630	4688	Core #1
4688	4780	Lime
4780	4868	Lime, Chert
	<u>4868</u>	<u>RTD - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas

Ran 9 Jts. New 20# 8 5/8" Casing overall 384.07 Set @ 392.07
Cement with 280 sacks Common Cement 3% C.C. 1/2# flo-Seal

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith #2 Well, located C NW NW of Section 26, Township 19 South, Range 33 West, Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS
SS
COUNTY OF BARTON

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 31st day of August, 1968.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1971