

15-171-20019-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Scott SEC. 26 TWP. 19S RGE. 33 E/W
Location as in quarters or footage from lines:
510' FN & 660' FW SE/4



Lease Owner Maurice L. Brown Company - #6234
Lease Name Smith Well No. 5
Office Address 200 Sutton Place, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed March, 1969
Application for plugging filed May 23, 1983
Plugging commenced 7-19-83
Plugging completed 7-20-83
Reason for abandonment of well or producing formation Non Commercial Value

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi

Producing formation _____ Depth to top 4599' bottom 4609' T.D. 4695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Oil	4094	4100	8 5/8"	382'	0'
Production	Oil	4599	4609	4 1/2"	4695'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 2 sks. hulls - 25 sks cement to 3850
Displaced to 1500' & pumped 25 sks. cement 1500 to 1100'
Displaced to 400' & pumped 25 sks. cement 400' to 0'
Pressured to 1400 lbs.
Cut off 8 5/8" & 4 1/2", 3' below ground level
Filled 8 5/8" w/10 sks. cement to ground level

RECEIVED
STATE CORPORATION COMMISSION
08-03-83
4116-0-1983
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
Lic. # 6497

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 83

Sandra L. Eves
Notary Public.

My Commission expires: 12-6-84



DRILLER'S LOG

COMPANY
CONTRACTOR
FARM
LOCATION
COMMENCED
COMPLETED

Yucca Petroleum Co.
LEBEN DRILLING, INC.
SMITH #5
G-NW-SE SECTION 26-19S-33W
Scott County, Kansas
2-6-69
2-19-69

0 150
150 1645
1645 2175
2175 2194
2194 2475
2475 2945
2945 3105
3105 3250
3250 3345
3345 3583
3583 3685
3685 3878
3878 4000
4000 4528
4528 4579
4579 4725
4725

Clay, Rock, Sand, Gravel
Shale
Shale, Lime Streaks
Anhydrite
Shale, Lime
Lime, Shale
Lime
Lime, Shale
Lime, Chalk Streaks
Lime
Lime, Shale
Lime
Lime, Chert
Lime
Lime, Shale Streaks
Lime
RTD

8 5/8" 20# new surface casing set @ 382.18' cemented with 270 sacks common cement, 37 cc

I Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith #5 Well, located C-NW SE of Section 26, Township 19 South, Range 33 West, Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 25th day of February, 1969.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1971

RECEIVED
STATE OF KANSAS
APR 23 1969
CONSERVATION DIVISION
Wichita Kansas