

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

XC: Dist. I

JUN 7 1985

API NUMBER 15-171-20,017-00-00

LEASE NAME Smith

WELL NUMBER 8W

810 Ft. from S Section Line

4580 Ft. from E Section Line

SEC. 26 TWP. 19 RGE. 33 XX or (W)

COUNTY Scott

Date Well Completed 4-14-69

Plugging Commenced 9-25-91

Plugging Completed 10-9-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Production Management, Inc.

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PHONE#(316) 265-4651 OPERATORS LICENSE NO. 6234

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filled? NR If not, is well log attached? Yes

Producing Formation Morrow Depth to Top 4644 Bottom 4676 T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	4642	4662	8 5/8	376	0
				4 1/2	4750	0

OCT 15 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dump sand & bridge back to 3105'. Halliburton dump 4 sx. cement from 3105 to 3083 (Est.) Perf. 4 holes @ 1350-51'. Pump 255 sx. down 4 1/2" (T/cem 450'). Pump 100 sx. dn. annulus (SIP - 100#). 8 5/8" & 4 1/2" cut off 3' BGL. Pump 1 1/2 yds. Redi-Mix dn. 4 1/2" & filled from 450' to surface. Weld plate on 4 1/2". Plugging witnessed by Dan Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Liberal, KS 67901

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steve Park, Division Engineer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Park

(Address) 209 E. William, Suite 200, Wichita, KS



SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 91

Connie L. Crook
Notary Public

My Commission Expires: 12-12-92

Well Record

Location: 810' FSL & 660' FWL SW/4, Sec.26-19S-33W,
Scott County, Kansas

Elevation: 2969' GL - 2974' KB

Drilling Commenced: 3-22-69

Drilling Complete: 3-31-69

Rotary TD: 4750' KB P.B.T.D. 4704'

Surface Csg: 8-5/8" 20#, 367' set @ 376' w/270 sx. Circ.
Long String: 4½" 9.5# 4764' Set @ 4750' KB w/200 sx. Pozmix.
T/cement - 3810'.

Perforations: Cherokee (Morrow Sd) 4642-62' w/32 holes.

Treatment: 2500 GNE acid.
21,000 GO & 19,500# Sd.

State Potential Test: 4-14-69 Pump 82.4 BO, no wtr./8 hrs.
12-30-74 to 1-3-75 Swab tested 18-25
BFPH w/trace of oil.

Sandology

B/Ft. Hays	370'	(+2604)
Anhy.	2106'	(+ 868)
B/Anhy.	2196	(+ 778)
Tarkio	3422	(- 448)
Heebner	3834	(- 860)
LKC	3876	(- 902)
B/LKC	4296	(-1332)
Marmaton	4320	(-1346)
Cherokee	4437	(-1463)
Morrow Sd.	4644	(-1670)
B/Morrow Sd.	4676	(-1702)
Mississippi	4680	(-1706)
RTD	4750	(-1776)

RECEIVED
STATE CORPORATION COMMISSION

SEP 09 1991

CONSERVATION DIVISION
Wichita, Kansas

15-171-20017-0000

Well File

RECEIVED MILLER'S LOG
STATE CORPORATION COMMISSION

SEP 09 1969

COMPANY
CONTACT
FA #
LOCATION
COMPLETED
COMPLETED

CONSERVATIC.
Wichita, K.

Yucca Petroleum Company
LEBEN DRILLING, INC.
SMITH #8
APPROX C SW SW SECTION 26-19S-33W
SCOTT COUNTY, KANSAS
3-22-69
3-31-69

0	50	Sand, Clay
50	375	Sand, Shale
375	1800	Shale, Sand
1800	2183	Shale, Lime Streaks
2183	2202	Anhydrite
2202	2635	Shale, Lime
2635	3000	Lime, Shale
3000	3430	Shale, Lime
3430	3578	Lime, Shale
3578	3765	Lime
3765	3972	Lime, Shale
3972	4751	Lime
	<u>4751</u>	<u>.TD</u>

8 5/8" 20# new surface casing set @ 375.45' cemented with 270 sacks Common cement, 3% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith #8 Well, located App C SW SW of Section 26, Township 19 South, Range 33 West, Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas this 8th day of April, 1969.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1971