

15-171-20188 00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Scott County, Sec. 25 Twp. 19S Rge. 33 E&W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SW

Lease Owner The Maurice L. Brown Co.
Lease Name SMITH "A" Well No. 2
Office Address 200 Sutton Place, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 6-13 19 80
Application for plugging filed 6-13 19 80
Application for plugging approved 6-13 19 80
Plugging commenced 6-13 19 80
Plugging completed 6-13 19 80
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4900'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4900'
Set 1st plug at 900' with 60 sx.
2nd plug at 500' with 30 sx.
3rd plug at 40' SB 10 sx.
Rathole with 5 sx., 50-50 sx. posmix,
6% gel

Plugging time 3:29 a.m. 6-13-80

RECEIVED
STATE CORPORATION COMMISSION

JUL - 7 1980

(If additional description is necessary, use BACK of _____ sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1980

My commission expires _____


Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Smith "A" #2
 LOCATION: SW SW, Section 25-19S-33W
 Scott County, Kansas
 SPUD DATE: 05-22-80
 COMPLETION DATE: 06-13-80

0	599	Surface Sand & Shale
599	2174	Sand & Shale
2174	2192	Anhydrite
2192	2235	Sand & Shale
2235	2688	Shale & Red Beds
2688	3050	Sand & Shale
3050	4900	Lime & Shale
	4900	Rotary Total Depth

Spud at 9:15 a.m., 05-22-80. Drilled 610' of 12-1/4" hole. Ran 15 joints of new 23# 604.20'. Cemented with 300 sacks of HLC, 3% Ca/ Cl., 14# Float per sack, followed with 150 sacks of Class H, 3% Ca. Cl. Cement did circ. Plug was down at 1:53 a.m., 05-23-80.

T.D. 4900' Laying down drill pipe preparing to plug plugging orders. 1st. plug 900' - 60 sacks 500-30 sacks 40' SB-10 sacks rathole 5-sacks, 50-50 sacks 6% gel. Plug was set at 3:29 a.m. 6-13-80.

SAMPLE TOPS:

Anhydrite 2175' (+782)
 B/Anhydrite 2192' (+765)


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SMITH "A" #2, SW SW, Section 25-19S-33W, Scott County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 26th day of June, 1980.



Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 7 1980
 CONSERVATION DIVISION
 Wichita, Kansas