

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-00017-000

LEASE NAME Smith #1-25

WELL NUMBER _____

SPOT LOCATION NW
C SW SW

SEC. 25 TWP. 19 RGE. 33 W (E) or

COUNTY Scott

Date Well Completed _____

Plugging Commenced 5/17/84

Plugging Completed 5/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cargill Natural Gas Operations bought by Kelso

Casing Pulling

ADDRESS 604 One Main Place, Wichita, Ks. 67202

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, S&D, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4705'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	400'	none
				5 1/2	4704'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plug job only- No pipe recovery. Pumped 2 hulls, 35 cement, 10 gel, & 120 sacks cement down 5 1/2". Pumped 200 sacks cement down back side.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

MAY 23 1984

Mike Kalen (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kalen

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1984

My Commission expires _____



Irene Hoover
NOTARY PUBLIC

15-171-00017-0021

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REPUBLIC NATURAL GAS CO.
Farm- Smith "A" No. 1

SEC. 25 T. 19 R. 33W
C SW NW

Total Depth, 4746'
Comm. 3-27-61 Comp. 4-14-61
Shot or Treated.
Contractor. Gabbert-Jones, Inc.
Issued. 6-8-63

County Scott KANSAS



K. G. S. LIBRARY

CASING:
8 5/8" 399' cem w/300 sec.
5 1/2" 4690' cem w/100 sec.

Elevation. 2961' RB

Production. DRY

Figures indicate Bottom of Formations.

top soil	30	"OWWO"
sand	125	CO: REPUBLIC NATURAL GAS
shale	640	WELL: #1 SMITH "A"
shale & shells	1000	CARD ISSUED: 2-18-82
shale	1450	WELL: F 7,536 MCFGPD
shale & shells	2245	CHASE 2665-2670
shale	2500	NEW INFO: RE-ENTERED 12-1-61, CO TO 2695 PBTB,
shale & lime	3110	MICT - CO, PF (KRI) 36/2655-70,
lime	3350	SWB DWN, NS, NAT, AC 1500 G, SWB DWN
lime & shale	3485	& KO FLO 7,536 MCFGPD, 12-8-61
lime	3602	
lime & shale	3892	
lime	4262	
lime & shale	4312	
lime	4426	
lime & shale	4471	
lime	4540	
lime & shale	4615	
lime	4635	
lime & shale	4680	
lime	4746	
Total Depth		
TOPS: ELECTRIC LOG		
Krider	2654	
Winfield	2705	
Admire	3180	
Heebner	3828	
Lansing	3920	
Marmaton	4305	
Cherokee	4421	
Pennsylvanian Sand	4586	
Ste. Genevieve	4612	