

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-27-94 (date)

by Hal Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4802'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	370'	8-5/8"	370'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Plugged and abandon using 60/40 Pozmix 6% gel, 1/2# Flocele per sack. Set 1st plug @ 2000' w/ 50 sks; 2nd plug @ 1350' w/50 sks; 3rd plug @ 400' w/50 sks and 4th plug @ 50' w/10 sks. 10 sacks in mousehole and 15 sacks in rathole. Plugging complete @ 9:00 A.M. on 10-27-94.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 3017 N. Cypress, Wichita, KS 67226-4003


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts stated herein, and matters herein contained and the log and data of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]
11-04-94 NOV 03 01:29 PM
(Address) 3017 N. Cypress
Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 94



Deborah Ann Paulus
Notary Public

My Commission Expires: January 8, 1996