

API NUMBER 15-171-20,437 0090

LEASE NAME Christy

WELL NUMBER 1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 22 TWP. 19 SRGE. 34 (E/S of W)

COUNTY Scott

Date Well Completed 9/22/91

Plugging Commenced 9/22/91

Plugging Completed 9/22/91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506, Russell, KS 67665-0506

PHONE# (913) -483-5345 OPERATORS LICENSE NO. 6111

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-22-91 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	246'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 5000'-3035' 50 sks cement @ 630'

100 sks cement @ 3035' 50 sks cement @ 260'

50 sks cement @ 2330' 10 sks cement @ 40'

80 sks cement @ 1270' 15 sks in rathole

(If additional description is necessary, use BACK of this form.) 10 sks in mousehole

Name of Plugging Contractor Emphasis Oil Oeprations License No. 750-750

Address P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Kyle B. Branum (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Kyle B. Branum  
 Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 91



[Signature]  
 Glenda R. Tiffin, Notary Public

Commission Expires: 2-6-92

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.  
P. O. Box 506  
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Christy WELL #1

LOCATION: NE NE SW  
Section 22-19S-34W  
Scott County, Kansas

LOGGERS TOTAL DEPTH: 4999'

ROTARY TOTAL DEPTH: 5000'

COMMENCED: 9/11/91

CASING: 8-5/8" @ 246' w/170 sks cement

ELEVATION: 3090' K.B.

COMPLETED: 9/22/91

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	252'	Lansing-Kansas City	4004'
Anhydrite	2308'	Base Kansas City	4426'
Shale	2322'	Marmaton	4466'
Heebner	3960'	Mississippi	4850'
Toronto	3971'	R.T.D.	5000'


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)

RECEIVED  
STATE COMMISSION

SEP 25 1991

Wichita


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on September 24, 1991.

My commission expires: February 6, 1992.

GLENDA R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

  
Glenda R. Tiffin, Notary Public