

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 5171204640000

LEASE NAME Farr

WELL NUMBER # 2

4950 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 22 TWP. 19S RGE. 34 (E) or (W)

COUNTY Scott

Date Well Completed 7-5-94

Plugging Commenced 8-15-95

Plugging Completed 8-15-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR J.W. OIL / Jim Farr

ADDRESS 209 Antelope

PHONE#(316) 872-2468 OPERATORS LICENSE NO. 30782

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-19-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Marrow Sand Depth to Top 4775 Bottom 1708 T.D. 4945

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	206	8 5/8	206	0
		0	4943	5 1/2	4943	1250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
pump 50 sx with 200 # hulls and displaced to 3800' (cement)
pump 80 sx at 1250' and displaced "
pump 55 sx gel followed by 40 sx cement to 600'
pump 40 sx from 230' to surface -- pump 10 sx at 40' "
 (If additional description is necessary, use BACK of this RECEIVED

Name of Plugging Contractor Post & Mastin Well Service Inc. License No. 08438


Address 3210 W Jones Av. Garden City, Kansas 67846 SEP 26 1995 09-26-95

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J W Oil / Jim Farr CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas COUNTY OF Scott, ss.

Marvin J. Farr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marvin J. Farr
 (Address) 913 Elizabeth Scott City, KS 67207

SUBSCRIBED AND SWORN TO before me this 25 day of SEPT, 19 95

Tamara L. Rice
 Notary Public
 My Commission Expires: _____