

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-091-20, 187-00-06  
LEASE NAME Robinson Farms  
WELL NUMBER # 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ft. from S Section Line  
2310 Ft. from E Section Line  
SEC. 15 TWP. 19S RGE. 24 (E) or (W)  
COUNTY SCOTT  
Date Well Completed 1991  
Plugging Commenced 4-23-98  
Plugging Completed 4-23-98

LEASE OPERATOR KYKON OIL & GAS, Inc.  
ADDRESS P.O. Box 1197  
PHONES (406) 248-3757 OPERATORS LICENSE NO. 71791

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on FEBRUARY 25, 1998 (date)  
by DAVID P. WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_  
Producing Formation NEVER PRODUCED THAT WE KNOW OF Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		1	562	8 5/8	562	- 0 -
		1	4831	5 1/2	4831	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
THE WELL HAD 250 SKS CEMENT IN IT WITH THE TOP AT ± 3445 (IN CASING) WELL WAS SECOND STAGED ON 5-10-80 SET PO @ 2222' KB 500 SKS. FINAL PLUG - PUMP 75 SKS DOWN BACKSIDE + SHUT IN. PUMP 100 SKS DOWN 238" + DISP. PULL UP 1200' CIRC CEMENT W/ 90 SKS, PULLED 78L AND TOPPED OFF W/ 10 SKS.

Name of Plugging Contractor MURFIN DRILLING Co. License No. 30606  
Address 250 N. WATER, STE 300, WICHITA, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KYKON OIL & GAS, Inc.

STATE OF MONTANA COUNTY OF YELLOWSTONE, ss.

KIRBY W. SCHMITZ, PRESIDENT OF KYKON OIL & GAS, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) P.O. Box 1197, Billings MT 59103

SUBSCRIBED AND SWORN TO before me this 27th day of JULY, 19 98

[Signature]  
Notary Public

My Commission Expires: 11/28/98

DRILLER'S LOG

WICHITA INDUSTRIES, INC.  
Robinson Farms No. 1  
SW NW SE  
Sec. 15-19S-34W  
Scott Co., Ks.

Commenced: 3-23-80  
Completed: 4-4-80

Surface Casing: 562' of 8-5/8"  
cemented w/450 sx Class H, 3% cc,  
1/4#/Flo seal per sack

FORMATION

DEPTH

Surface Hole	0 - 571
Shale	571 - 800
Shale & Sand	800 - 1448
Sand & Shale	1448 - 1875
Shale	1875 - 3270
Lime & Shale	3270 - 4024
Lime	4024 - 4205
Lime & Shale	4205 - 4405
Lime	4405 - 4840 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*Ella Priess*

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 7th day of April, 1980.

*Dorothy L. Schmidt*  
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. April 30, 1983

15-171-20187-00-00

12	11	10	9	8	7	6	5	4	3	2	1	0	1	2	3	4	5	6	7	8	9	10	11	12
12	11	10	9	8	7	6	5	4	3	2	1	0	1	2	3	4	5	6	7	8	9	10	11	12