

State of Kansas



15-1169-20011-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

September 18, 1969

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: George Hess

Complete Address: 505 N. Charles, McPherson, Kansas 67460

Lease Name: Agnes Johnson Well No. 1

Location: SW SE SW Sec. 11 Twp. 15 Rge. 2  (W)  X

County: Saline Total Depth 2830' Oil Well  X

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2800' and cement with 5 sacks cement.

Fill hole with mud to 125'. Set rock bridge from 125' to 115' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 30 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 09-30-1969