

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-119-30004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
FAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 7, 1965

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1965
01-13-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Harvey German of German Drilling Company has this
date requested permission to plug the following described well:

Mr. German guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 412 One Twenty Bldg., Wichita, Kansas

Lease Name: Cline Well No. 1

Location: C NW SE Sec. 16 Twp. 15 Rge. 2 (E) (W) X

County Saline Total Depth 2795' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. German was instructed to plug the well as follows:

Fill hole with mud to 215'. Set hull bridge at 215' and
cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent