



15-169-20013-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 6, 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

DEC 13 1967  
12-13-1967

Dear Sir:

Mr. Bill Makely of Melland Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: Melland Drilling Company, Inc.

Complete Address: P.O. Box 783, Mc Pherson, Kansas

Lease Name: Melander Well No. 2

Location: NW NW NE Sec. 24 Twp. 15 Rge. 2 (E) (W) X


County: Saline Total Depth 2715' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Makely was instructed to plug the well as follows:

Fill hole with mud to 120'. Push plug and 1/2 sack hulls to 120' and  
cement hole with 20 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

  
Conservation Division Agent