



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 9, 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1963
09-18-1963
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Melland Drilling Company

Complete Address: 1111 N. Main, Hutchinson, Kansas

Lease Name: Raetz Well No. 1

Location: CSW SE Sec. 24 Twp. 15 Rge. 2 (E) (W) X

County Saline Total Depth 2759' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2740' and cement with 5 sacks.

Fill hole with mud to 150'. Set rock bridge from 150' to

140' and cement with 20 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks

cement.

Very truly yours,

William J. Lomen
Conservation Division Agent