



15-169-20162-00-00

JOHN CARLIN
R C LOUX
JANE T ROY
PHILLIP R. DICK
CAROL J LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

February 7, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Gib Overby of Mustang Drilling + Expl. has this date requested permission to plug the following described well:

Operator's Full Name: Petromark Exploration, Inc.

Complete Address: 7030 South Yale, Suite 711, Tulsa, Oklahoma 74177

Lease Name: Glenn Well No. 1

Location: C NW NE Sec. 25 Twp. 15 Rge. 2 (W)

County: Saline Total Depth: 3560'


Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Overby was instructed to plug the well as follows:

8 1/8" - 271' - 200 sacks 3% c.c. 2% gel (Common) Fill hole with mud.
Pump 50 sacks 50/50 Pozmix w/2% gel + 3% cc through drill
pipe at 300'. Fill hole with mud to 40'. Push plug and
1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Cement rat hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
02-22-1982
FEB 22 1982
CONSERVATION DIVISION
Wichita, Kansas