



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

August 13, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1963
 08-19-1963
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bill Makely of Melland Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: Box 620, McPherson, Kansas

Lease Name: Krauss "C" Well No. 1

Location: C NW NW Sec. 25 Twp. 15 Rge. 2 (E) (W) X

County Saline Total Depth 2771' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Makely was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 150'. Push

plug and 1/2 sack hulls to 150' and cement with 20 sacks

through drill pipe. Fill hole with mud to 35'. Push plug

and 1/2 sack hulls to 35' and cap hole with 8 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Arthur J. Lomen
 Conservation Division Agent