



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 13, 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1963
10-21-1963
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling Inc. has this

date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.Operator's full Name: Mull Drilling Co., Inc.Complete Address: 1625 Wichita Plaza Bldg., Wichita, KansasLease Name: E. V. Wendt Well No. 1Location: NW SW SE Sec. 36 Twp. 15 Rge. 2 (D) (W) XCounty Saline Total Depth 2794' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Plouffe was instructed to plug the well as follows:Circulate heavy mud. Fill hole with mud to 125'. Pushplug and $\frac{1}{4}$ sack hulls to 125' and cement with 20 sacksthrough drill pipe. Fill hole with mud to 40'. Pushplug and $\frac{1}{4}$ sack hulls to 40' and cap hole with 10 sacks.Fill and bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent