



15-169-00442-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

September 29, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Rochwile, Inc.

Complete Address: 503 Mayo Bldg., Tulsa, Oklahoma 74103

Lease Name: Norton "A" Well No. 1

Location: C SE SE NW Sec. 32 Twp. 14 Rge. 2 (E) (W) X

County: Saline Total Depth 3211 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3200' and cement with 5 sacks cement.

Fill hole with mud to 200'. Set rock bridge from 200' to 190' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent