

15-171-20024-00-00

Form CP-3
Rev. 6-4-68

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Yucca Petroleum Company,

Complete Address Box #2585, Amarillo, Texas.

Lease Name Smith Well No. 11

Location CNW-SW Sec. 26 Twp. 19 Rge. (E) (W) 33

County Scott Total Depth 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 8:00 PM Day 19 Month 9 Year 1969

The above well was plugged as follows:

402'--8 5/8" Surface casing, cement circulated with 270 Sx.
Yucca elected to use cement in plugging off certain bottom hole zones, their Engineer
to pick the zones.

Circulated hole from bottom with heavy mud. Pulled DP to 4650' and displaced 25 Sx.
cement thru DP from 4650' to 4570'. Pulled DP to 4250' and displaced 55 Sx. cement
thru DP from 4250' to 4070'. Pulled DP to 950' and displaced 55 Sx. cement thru DP
from 950' to 770'. Pulled DP to 402' and displaced 20 Sx. cement thru DP from 402'
to 362'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/23/69

INV. NO. 527-W

Signed: W. L. Dinkel
Well Plugging Supervisor