

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Yucca Petroleum Company

Complete Address Box #2585, Amarillo, Texas.

Lease Name Smith Well No. 13

Location 150' West of CSE-NE Sec. 26 Twp. 19 Rge. (E) (W) 33

County Scott Total Depth 4710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 11:30 PM Day 1 Month 11 Year 1969

The above well was plugged as follows:

354'--8 5/8" Surface casing, cement circulated with 270 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 4600' and displaced 30 Sx. cement thru


DP from 4600' to 4510'. Pulled DP to 1000' and displaced 120 Sx. cement thru DP from

1000' to 600'. Pulled DP to 390' and displaced 30 Sx. cement thru DP from 390' to 300'.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 11/6/69
NO. 782-u

Signed: 
Well Plugging Supervisor