

15-171-20009-00-00

Form CP-3
Rev. 6-26-62

KANSAS

AL

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

*RWD
09-03-68*

Operator's Full Name Yucca Petroleum Company,

Complete Address: Box #2585, Amarillo, Texas. 79105

Lease Name Smith Well No. 2

Location CNW-NW Sec. 26 Twp. 19 Rge. (E) (W) 33

County Scott Total Depth 4868

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas, License No.

Operation Completed: Hour 12:00PM Day 30 Month 8 Year 1968

The Above well was plugged as follows:

392'--8 5/8" Surface casing, cement circulated with 280 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Ran plug on bottom with 50 Sx. cement from 4595' to
4400'. Pulled DP to 1000' and displaced 100 Sx. cement thru DP from 1000' to 675',
pulled DP to 420' and displaced 30 Sx. cement thru DP from 420' to 310'. Pulled DP,
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. A. D... ..*
Well Plugging Supervisor

INVOICED
DATE 9/3/68
INV. NO. 8398-11