

15-171-20035-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc., & Petroleum Resources, Co.,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Lehman Well No. E-1

Location SW-SE-SE Sec. 30 Twp. 19 Rge. (E) (W) 34

County Scott Total Depth 5039'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Co., Inc.,

Address 1425 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 5:00 PM Day 9 Month 3 Year 1972

The above well was plugged as follows:

418'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota Section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 435' and displaced 30 Cu. Ft. cement thru
DP from 435' to 360'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *J. L. Dilsch*
Well Plugging Supervisor

RECORDED
DATE 3/14/72
NO. 5343-W