

15-171-20032-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird and Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Minnix Well No. 1

Location NW-SW Sec. 28 Twp. 19 Rge. (E) (W) 34

County Scott Total Depth 5025'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 3:30 PM Day 8 Month 12 Year 1971

The above well was plugged as follows:

414'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 435' and displaced 30 Cu. Ft. cement thru
DP from 435' to 360'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. G. Nichols*
Well Plugging Supervisor

RECORDED
DATE 12/10/71
SERV. NO. 4802-W