

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-169-20,162-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Petromark Exploration, Inc.  
 Complete Address 7030 South Yale, Suite 711, Tulsa, Oklahoma 74127  
 Lease Name Glenn Well No. 1  
 Location C. NW NE Sec. 25 Twp. 15 Rge. 2 (~~East~~) (West)  
 County Saline Total Depth 3560'  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
 Other well as hereinafter indicated \_\_\_\_\_  
 Plugging Contractor Mustang Drilling + Exploration and Sun Oilwell Cementing  
 Address Box 1069, Great Bend, Kansas License No. \_\_\_\_\_  
 Operation Completed: Hour: 4:15 PM Day: 7 Month: February Year: 1982  
 Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

Hole circulated and Filled with mud. 50 sacks 50/50 Pozmix  
w/290gal and 3% c.c. pumped through drill pipe at 300'  
Hole Filled with mud to 40' Plug and 1/2 sack hulls pushed to 40'  
and hole cemented to base of cellar with 10 sacks cement.  
Rathole cemented with 10 sacks cement.

Amount of Surface Casing: 8 3/4" - 218' - 225 sacks Common 290gal 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: [Signature]  
Conservation Division Agent

INVOICED  
DATE 2-23-82  
INV. NO. 9466-W

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 22 1982  
CONSERVATION DIVISION  
Wichita, Kansas