


15-169-00442-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County. Sec. 32 Twp. 14 Rge. 2W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines CSESE NW
Lease Owner Rochwile, Inc.
Lease Name Norton "A" Well No. 1
Office Address Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Sept. 28 19 70
Plugging completed Oct. 1 19 70
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back in the 5 1/2 with sand and dumped 5 sacks of cement.
Shot pipe off at 712.80'. Pulled pipe and mudded hole to
220'. Set rock bridge from 220' tp 200' and dumped 25 sacks
of cement. Finished mudding hole and dumped 10 sacks of
cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Bert Self

R. R. #4, Hutchinson, Kans. 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 70.

My commission expires October 18, 1973

Notary Public.



15-169-00442-00-00

Driller's Log -- COMM: 9-16-47 8 5/8" - 202' 1" - Cem. 115 sx.
COMR: 9-25-47 5" -3236' - Cem. 100 sx.

Elev. 1262.4 DF.
1259.1 GR.

- 30 - Shale and lime
- 140 - Sand, shale, shells
- 180- Anhydrite
- 215 -
- 375 - Sahle and lime
- 575 - Lime
- 670 - Lime and shale
- 830 - Shale and shells
- 975 - Shale
- 1035 - Shale, sandy
- 1265 - Shale
- 2030 - Shale and lime
- 2370 - Lime
- 2605 - Shale
- 2705 - Shale and Lime
- 2830 - Lime
- 2890 - Lime and chert
- 2960 - Shale and lime
- 3035 - Shale
- 3155 - Lime
- 3236 - Shale

- BITS:**
- 1. 215 - 620
 - 2. 620 - 670
 - 3. 670 -1575
 - 4. 1575 -2100
 - 5. 2100 -2480
 - 6. 2480 -2715
 - 7. 2715 -2890
 - 8. 2890 -3120
 - 9. 3120 -3239 TD

GEOLOGICAL TOPS:

- 1991- Kansas City - Lansing Limes
- 2623 - Mississippi Lime
- 2870 - Kinderhook
- 3050 - Tunton Lime
- 3152 - Sylvan Shale
- 3236 - Viola Lime

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1970
 CONSERVATION DIVISION
 Wichita, Kansas