

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Finney County, Sec. 31 Twp. 21 Rge. 30W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW NE

Lease Owner Bennett & Roberts Drilling Co.

Lease Name Drees Well No. 1

Office Address Russell, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4/24 19 56

Application for plugging filed 4/24 verbally 19 56

Application for plugging approved 4/24 verbally 19 56

Plugging commenced 4/24 19 56

Plugging completed 4/24 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4885 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	290'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud up to 280', 1/2 sack of hulls.
1 Plug, 20 sacks cement, mud up to 35'.
1 Plug & 1/3 sack hulls and 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Harold Wurst (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst

Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 56

My commission expires 6/17/58

Notary Public.

05-01-56

PLUGGING
FILE SEC 32 T 21 R 30W
BOOK PAGE 57 LINE 9

Bennett & Roberts Drilling Co.
Drees #1

SW SW NE 31-21-30
Finney County, Ks.

R.T.D. 4885'

Commenced 4/1/56
Completed 4/24/56

Tops as per electric log	
Cimarron Anhydrite	2070
Herington	2718
Krider	2746
Winfield	2771
Heebner	3976
Lansing K.C.	4022
Basal K.C.	4450
Marmaton	4472
Fort Scott	4548
Cherokee	4582
St. Louis	4734

Casing Record
10 3/4" Set @ 290' w/200 sx cmt.

----- Figures Indicate Bottom of Formation -----

Surf. clay, stks. limestone	40
Sand	155
Grey Shale	220
Gyp. Stks grey shale, Yellow clay	270
Blue Shale	290
Shale & Shells	1300
Red Shale & Lime Streaks	1335
Shale & Shells	1560
Red Bed & Shale	2040
Shale & Lime Streaks	2110
Red Shale & Lime	2175
Shale & Shells	2685
Shale, Sand & Lime	2838
Lime & Shaled	3345
Hard Lime	3375
Lime	3700
Lime & Shale	3750
Lime & Shale (Chalky)	3875
Lime	4885

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By *W. L. Lake*

Subscribed and sworn to before me this 30th day of April, 1956.

Clara Leonard
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE REC-327-21-30W
BOOK PAGE 57 LINE 9

MINERAL DIVISION
Wichita, Kansas