

15-169-19029-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Saline SEC. 30 TWP. 14S RGE. 2W E/W  
 Location as in quarters or footage from lines:  
C S/2 SE SW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Gear Petroleum Company, Inc.  
 Lease Name Balaun #2 Well No. \_\_\_\_\_  
 Office Address 300 Sutton Place Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 3-7-83  
 Plugging completed 3-15-83  
 Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3225'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	204'	none
				4-1/2"	3219'	2309'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Plugged off bottom with sand to 3170' and ran 6 sacks cement. Shot casing @2712', 2510', 2411', 2309' and pulled a total of 70 joints of 4-1/2" casing. Plugged well with 3 hullo, 20 gel, released plug and displaced with 100 sacks cement, 50/50 pos, 2% gel.~~

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
 Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1983

My Commission expires: 

Irene Hoover  
 Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 21 1983

CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

**COPY**


15-169-19029-00-00

Company- KREBBS & ELLIS  
Farm- Delaun No. 2

SEC. 30 T. 14 R. 2W  
CS/2 SE SW

Total Depth. 3225  
Comm. 10-11-63 Comp. 10-20-63  
Shot or Treated.  
Contractor. White & Ellis  
Issued. 5-23-66

County Saline KANSAS



Elevation. 1234' KD

CASING:  
3 5/8" Q 204' w/150 sx.  
4 1/2" Q 3219' w/50 sx.

Production. FMP 25 BOPD & 50% Wtr.  
(MAQ 3219-25)

Figures indicate Bottom of Formations.

cellar	5
soil & sand	50
sand & shale	100
lime & shale	175
lime	203
Anhydrite	235
sdv shale strks. & red rock	350
shale & lime	1185
limed shale	1300
shale & lime stks.	1470
shale & sandy stks.	1510
lime & shale	1670
lime	1620
shale & lime	1960
lime	2060
shale	2180
lime & shale stks.	2315
lime & shale	2657
lime	2921
shale	3101
lime	3142
shale	3217
dolomite & chert	3225
Total Depth	

TOPS: LOG

Kansas City	1960
Mississippi	2657

SAMPLE TOPS:

Conglomerate	2657
Mississippi	2666
Kinderhook Sand	2921
Hunton	3035
Maquoketa Shale	3142
Maquoketa Dolomite	3219

RECEIVED  
STATE CORPORATION COMMISSION

AUG 04 1982

CONSERVATION DIVISION  
Wichita, Kansas

Phone 913-483-2627, Russell, Kansas  
 Phone 316-793-5861, Great Bend, Kansas

15-169-19029-00-00  
 Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

# ALLIED CEMENTING CO., INC.

No 34579

Home Office P. O. Box 31

Russell, Kansas 67665

*CID.*

Date	3-15-83	Sec.		Twp.		Range		Called Out	6:25	On Location	11:50am	Job Start		Finish	12:35	
Lease	Behaven	Well No.	= 2		Location	S1 + 1/2 E 1/4 Sec. 17 1/2 E 1/2 S		County	Sawyer		State	KS				
Contractor	Kelen							Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Type Job	Plug to abandon							Charge To	C. P. O.							
Hole Size	T.D.							Street								
Csg. Size	5 7/8							City	State							
Tbg. Size	Depth							The above was done to satisfaction and supervision of owner agent or contractor.								
Drill Pipe	Depth							Purchase Order No.	X							
Tool	Depth							CEMENT								
Cement Left in Csg.	Shoe Joint							Amount Ordered	100# 50/50 #2 20 Gal. 3 Hulls							
Press Max.	500 #							Consisting of								
Meas Line	Displace							Common	50							
Perf.								Poz. Mix	50							
<b>EQUIPMENT</b>																
Pumptrk	No	Cementer	Curtis Russell													
Pumptrk	No	Helper	Russell													
Bulktrk	No	Cementer	mike N													
Bulktrk	No	Helper														
Bulktrk	No	Driver														
Bulktrk	No	Driver														
<b>DEPTH of Job</b>																
Reference:	1 pump truck chg		150.00													
	1 8 7/8 plug		10.00													
	Sub Total															
	Tax															
	Total															
Remarks:	mixed 3 Hulls, 20 Gal, Released Plug 100# cement, shot in @ 300 #															

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 24 1983