

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-169-00792-00-00

API NUMBER None

COUNTY Saline

LEASE NAME Balaup WELL# 1

SPOT LOCATION SE NE SW

SEC. 30 TWP. 14 RGE. 2 (E) OR (W)

PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.  
TYPE OR PRINT

LEASE OPERATOR Gear Petroleum Co., Inc.

PHONE # ( ) 316-265-3351

OPERATORS LICENSE NO. 5151

CHARACTER OF WELL OIL (OIL), GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 9/25/50 PLUGGING COMMENCED 7/6/83 and 7/13/83

PLUGGING COMPLETED 7/13/83 REASON FOR ABANDONMENT OF WELL OR PRODUCING FORMATION- Maquoketa - uneconomic

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Gilbert Toman

IS ACC-1 FILED?                      IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION Maquoketa DEPTH TO TOP 3219' BOTTOM 3225' T.D. 3225

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maquoketa	oil	3219	25	8 5/8	200	None
				5 1/2	3219	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Push wood and rubber plug to 500', fill 5x casing with ready mix. Pump 5 sx pozmix in annulus between 5 1/2 and 8 5/8

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Gear Petroleum Co., Inc. LICENSE NO. 5151  
ADDRESS 300 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, SS.

Jim Thatcher, Drlg & Prod Mgr. (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT. SO HELP ME GOD.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 2 1983

CONSERVATION DIVISION  
Wichita, Kansas

(SIGNATURE) Jim Thatcher

(ADDRESS) 300 Sutton Place, Wichita, KS 67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 31st DAY OF August, 19 83

Helen L. Coyer  
NOTARY PUBLIC

Helen L. Coyer

MY COMMISSION EXPIRES: April 1, 1986

HELEN L. COYER  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appl. Exp. 4-1-86

FORM CP-4  
REVISED 06-83


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. PHILLIPS & SANDERSON  
Farm. Helen Baulan No. 1

SEC. 30 T. 14 R. 2W  
SE NE SW

Total Depth. 3225  
Comm. 9-13-50 Camp. 9-25-50  
Shot or Treated.  
Contractor. E. K. Carey  
Issued. 12-12-53

County Saline  
KANSAS



Elevation. 1233 DF

8 5/8" 200' cem. w/200 sx, circ.  
5 1/2" 3219' cem. w/ 50 sx

Production. Swb. 54 BO / 234 wtr.

Figures indicate Bottom of Formations. K.B.

rotary table, base & cellar	8
clay	18
sand	50
sand & gravel	95
shale & shells	150
lime	280
lime & shale	415
lime	416
lime & shale	1385
shale	1510
lime & shale	1560
lime	1670
shale & redrock	1692
shale & lime	1725
lime	1785
shale	1815
lime	1816
lime & shale	2050
lime	2285
shale & lime	2715
lime	2870
lime & shale	2895
lime	2934
shale & lime	3058
lime	3140
lime & shale	3219
lime	3225
Total depth	

Geologist Tops: K.B.	
Miss. lime	2655
Kinderhook	2932
Hunton	3044
Maquoketa shale	3139
Maquoketa dolomite	3219
Pay 3219-25	
Rotary Total depth	3225

RECEIVED  
STATE CORPORATION COMMISSION

AUG 04 1982

CONSERVATION DIVISION  
Wichita, Kansas