

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-00643-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline County, Sec. 30 Twp. 14 Rge. 2 #E (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S W SW NE

Lease Owner Mallard Drilling Company

Lease Name Quinn Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) DRY

Date well completed October 26 1951

Application for plugging filed November 30 1951

Application for plugging approved 1951

Plugging commenced 12-8-51 1951

Plugging completed 12-13-51 1951

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1951

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation Depth to top Bottom Total Depth of Well 3223 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	142'	None
				5-1/2"	3220'	2634'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3250' to 3210' and ran 6 sacks of cement. Bailed hole. Mudded hole to 150', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 20' and ran 5 sacks of cement. Plugging completed.

DEC 18 1951

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. C. Nelson, partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

SUBSCRIBED AND SWORN to before me this 17th day of December, 1951

My commission expires 12/4/52 Raywell Wright Notary Public.

28-8390-s 6-51-20M

30 - 14 220
131 35

St. C. and

15-169-00643-00-00

COMPANY: Mallard Drilling Company
 CONTRACTOR: Mallard Drilling Company
 FARM: Quinn #1
 LOCATION: SW SW NE Sec. 30-14-2W
 Saline County, Kansas
 COMMENCED: September 29, 1951 --rotary
 October 17, 1951--cardwell
 COMPLETED: October 10, 1951--rotary
 October 26, 1951--cardwell

0	90	142	Shale and shells
142	to	420	Lime
420	to	790	Lime and sand
790	to	905	Lime and sand
905	to	1435	Shale and shells
1435	to	1675	Lime and shale
1675	to	2700	Shale and lime
2700	to	2740	Mississippi
2740	to	2970	Lime
2970	to	3120	Lime
3120	to	3205	Lime and shale
3205	to	3218½	Shale and lime
3218½	to	3223	Shale and lime --T.D. rotary
3223	to	3250	Chat, water
		3250	T.D. --cardwell

Set 142' of 8 5/8" surface pipe. Cemented with 110 sacks cement

Set 5½" pipe at 3220. Cemented with 50 sacks cement.

TOPS; Viola 3218½
3223--3224 Show of water and oil

Measurements taken from derrick floor.

Acidized with 750 gallons at 3224. Water, show of oil DEC 15 1951

DRY AND ABANDONED

SE
 DIVISION
 DIVISION
 KANSAS

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Quinn #1, Sec. 30-14-2W, Saline County, Kansas. as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 2nd day of November 1951.

My commission expires 1/7/52 Maxwell Wright

PLUGGING
 FILE 30-30-14-2W
 BOOK PAGE 131-135