

OR  
FORMATION PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH

OX			

Locate well correctly on above  
Section Plat

Saline County. Sec. 30 Twp. 14S Rge 2W (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SW/4

Lease Owner Westgate-Greenland Oil Company

Office Name Rinhardt Well No. 1

Office Address 508 Wolcott Bldg. Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 23 19 43

Application for plugging filed Oral permission April 23 19 43

Application for plugging approved April 23 19 43

Plugging commenced April 23 19 43

Plugging completed April 23 19 43

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. L. Durkee

Producing formation Depth to top Bottom Total Depth of Well 3415 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	148 ft	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to bottom of surface pipe and put in 10 sacks cement finished filling hole within 10 feet of top. Put in 5 sacks cement and welded steel plate over top of surface casing.

30-14-2W  
7/14-35

04-27-43

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland oil Company  
Address 508 Wolcott Bldg. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ed Nelson

(Address)

SUBSCRIBED AND SWORN to before me this 26 day of April, 19 43

Evan V. Sage

Notary Public.

My commission expires My Commission Expires March 25th, 1946.



COMPANY: Westgate-Greenland Oil Company  
 CONTRACTOR: Nelson Drilling Company  
 FARM: Rinhardt #1  
 LOCATION: Section 30-14S-2W Saline County, Kansas  
 NW NW of SW/4  
 COMMENCED: April 9, 1943  
 COMPLETED: April 23, 1943

0	to	60	Sand
60	to	120	Shale
120	to	143	Lime
143	to	225	Shale
225	to	255	Red Bcd
255	to	610	Lime
610	to	800	Lime shells and shale
800	to	945	Shale and shells
945	to	1180	Shale
1180	to	1220	Lime
1220	to	1400	Shale
1400	to	1490	Shale and lime shells
1490	to	1600	Shale
1600	to	1755	Lime
1755	to	1840	Lime
1840	to	2120	Shale
2120	to	2150	Lime
2150	to	2180	Shale
2180	to	2400	Lime
2400	to	2445	Shale
2445	to	2570	Lime
2570	to	2724	Shale
2724	to	2890	Chat
2890	to	2900	Lime
2900	to	3100	Shale
3100	to	3185	Lime
3185	to	3218	Shale
3218	to	3375	Lime
3375	to	3415	Sand and shale
		3415	T. D.

Run and cemented 148 feet of 10 3/4 inch surface pipe. Cemented with 70 sacks cement.

DRY, ABANDONED, AND PLUGGED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Rinhardt #1, Section 30-14S-2W, Saline County, Kansas, as reflected by files of the Nelson Drilling Company.

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Reno County, Kansas this 26 day of April 1943.

PLUGGED  
 SEC 30 14S-2W  
 PAGE 71 OF 35

*E. V. Sage*