

15-169-19026-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Saline SEC. 30 TWP. 14S RGE. 2W E/W  
Location as in quarters or footage from lines:  
S/2 SW SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Gear Petroleum Company, Inc.  
Lease Name Sudendorf #2 Well No. \_\_\_\_\_  
Office Address 300 Sutton Place Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 3-3-83  
Plugging completed 3-15-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3310'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	250'	none
				5-1/2"	3309'	2592'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Plugged off bottom with sand to 3200' and ran 7 sacks cement. Shot casing @2811'  
2708', 2615' and pulled a total of 81 joints of 5-1/2" casing. Plugged well with  
3 hulls, 20 gal, released plug and displaced with 100 sacks cement, 50/50 pos, 2% gel.  
Plugging Complete.~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of March, 19 83

My Commission expires:



Irene Hoover  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1983

CONSERVATION DIVISION  
Wichita, Kansas

Phone 913-483-2627, Russell, Kansas  
 Phone 316-793-5861, Great Bend, Kansas

15-169-19026-00-00

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

# ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 34578


Date	3-15-83	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish
					6:25am	1:50pm		11:35am
Lease	Well No. #2	Location 81 + Magacha 1/2 E N/S			County	Saline	State	Ks
Contractor	Kelso				Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.		
Type Job	Plug to Abandon				Charge To	Geo. Petro		
Hole Size	T.D.				Street			
Csg. Size	8 5/8				City	State		
Tbg. Size	Depth				The above was done to satisfaction and supervision of owner agent or contractor.			
Drill Pipe	Depth				Purchase Order No.	X <del>111-111-111</del>		
Tool	Depth				<b>CEMENT</b>			
Cement Left in Csg.	Shoe Joint				Amount Ordered	100 50/50 LOG 1 3 HULLS		
Press Max.	400 #				Consisting of			
Meas Line	Displace				Common	50		
Perf.					Poz. Mix	50		
<b>EQUIPMENT</b>								
Pumptrk	No	Cementer	Curtis Russell					
	158	Helper						
Pumptrk	No	Cementer						
		Helper						
Bulktrk		Driver	Mike N					
Bulktrk	116	Driver						
DEPTH of Job								
Reference:	pump Trk chg		340 <sup>00</sup>					
	pump Trk mileage							
	1 8 5/8 plug							
	Sub Total							
	Tax							
	Total							
Remarks:	mixed 3 HULLS, 20 GEL Released Plug 100 amount of cement							
STATE CORPORATION COMMISSION								
MAR 24 1983								
CONSERVATION DIVISION Wichita, Kansas								

Company- **HOWARD KREBBS & LEO ELLIS**  
 Farm- **Sudendorf** No. **2**

SEC. **30** T. **14** R. **2W**  
 C **S/2** SW SE

Total Depth. **3310'**  
 Comm. **1-23-62** Comp. **1-31-62**  
 Shot or Treated.  
 Contractor. **White & Ellis Drig.**  
 Issued. **6-2-62**

County **Saline**  
**KANSAS**



**CASINO:**  
**8 5/8" 250' cem w/200 sx.**  
**5 1/2" 3309' cem w/75 sx.**

Elevation. **1235' RB**

Production. **35 BOPD, 20% wcr.**

Figures Indicate Bottom of Formations.

soil	80
sand w/lime strks.	100
lime	250
lime & shale	575
lime	650
lime & shale	930
shale & lime	1500
lime	1725
lime & shale	1825
shale	1925
shale & shells	2023
lime & shale	2060
lime	2250
lime & shale	2552
shale & lime	2649
lime & shale	2690
lime	2931
shale	3048
lime	3131
shale	3218
dolomite	3268
lime	3310
Total Depth	

**TOPS:**

Burgess Sand	2662
Mississippi	2649
Kinderhook Shale	2921
Hunton	3120
Maquoketa	3131
Maquoketa Dolomite	3217
Viola	3268

**RECEIVED**  
 STATE CORPORATION COMMISSION  
**AUG 04 1982**  
 CONSERVATION DIVISION  
 Wichita, Kansas