

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

15-169-00255-00.01
API NUMBER None
COUNTY Saline
LEASE NAME Sudendorff WELL# 1
SPOT LOCATION NW NW SE
SEC. 30 TWP. 14 RGE. 2 (E) OR (W)

LEASE OPERATOR Gear Petroleum Co., Inc.

PHONE # () 316 265 3351

OPERATORS LICENSE NO. 5151

CHARACTER OF WELL Oil (OIL), GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 3/4/43

PLUGGING COMMENCED 7/6/83

PLUGGING COMPLETED 7/6/83

REASON FOR ABANDONMENT OF WELL OR PRODUCING

FORMATION- Maquoketa - uneconomic

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Gilbert Toman

IS ACQ-1 FILED? No IF NOT, IS WELL LOG ATTACHED? attached

PRODUCING FORMATION Maquoketa DEPTH TO TOP 3225 BOTTOM 3234 T.D. 3234

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Maquoketa</u>	<u>oil</u>	<u>3225</u>	<u>34</u>	<u>10 3/4</u>	<u>150</u>	<u>None</u>
				<u>7</u>	<u>3225</u>	<u>None</u>

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Rock bridge at 500', cut off 7" 5' below top 10 3/4; fill 7" and 10 3/4 with ready mix concrete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Gear Petroleum Co., Inc. LICENSE No. 5151
ADDRESS 300 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, SS.

Jim Thatcher, Drilling & Production Manager (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT. SO HELP ME GOD.

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1983

CONSERVATION DIVISION
Wichita, Kansas

(SIGNATURE) Jim Thatcher
(ADDRESS) 300 Sutton Pl, Wichita, KS 67202

BEFORE ME THIS 31st DAY OF August, 19 83

Helen L. Coyer
NOTARY PUBLIC
Helen L. Coyer

MY COMMISSION EXPIRES: April 1, 1986



FORM CP-4
REVISED 06-83

STENCILED

ORIGINAL

MAY 8 1943.

Discovery Well

15-169-00255-00-01

COMPANY: Westgate-Greenland Oil Company
CONTRACTOR: Nelson Drilling Company
FARM: Sudendorf #1
LOCATION: Section 30-14S-2W Saline County
NW 1/4 SE
COMMENCED: February 17, 1943
COMPLETED: March 4, 1943

Dot 124 info 225B.W

0	to	65	Sand
65	to	580	Lime
580	to	600	Shale
600	to	650	Sandy lime
650	to	1225	Shale
1225	to	1340	Lime
1340	to	1535	Shale
1535	to	1690	Lime
1690	to	1710	Shale
1710	to	1790	Lime
1790	to	1810	Shale
1810	to	1920	Lime
1920	to	2025	Shale
2025	to	2170	Lime
2170	to	2265	Shale
2265	to	2420	Lime
2420	to	2725	Shale
2725	to	2735	Lime--Chat 2733
2735	to	2897	Chat
2897	to	2905	Shale
2905	to	2945	Lime
2945	to	3055	Shale
3055	to	3175	Shale
3175	to	3228	Shale
3228	to	3234	Lime
		3234	T. D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 04 1982

CONSERVATION DIVISION
Wichita, Kansas

Min 2 5 4
Boul 2 9 2
Hunt 2 6 5
B 1 3 1 5 5
V 3 2 2 3

Run and cemented 150 feet of 10 inch surface pipe. Cemented with 105 sacks cement.
Run and cemented 3225 feet of 7 inch casing. Cemented with 65 sacks cement.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Sudendorf #1, located in Section 30S-2W, Saline County, Kansas, as reflected by files of the Nelson Drilling Company.

Subscribed and sworn to before me, a Notary Public, within and for Reno County, Kansas, this _____ day of April 1943.