

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER #15-171-20,463 ~~00-00~~

LEASE NAME Fairleigh

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-14

554 Ft. from S Section Line

4726 Ft. from E Section Line

SEC. 14 TWP. 19S RGE. 34 (E1/4 (W))

COUNTY Scott

Date Well Completed 3-7-94

Plugging Commenced 3-7-94

Plugging Completed 3-7-94

LEASE OPERATOR Cholla Resources, Inc.

ADDRESS 1641 California St., Ste. #400, Denver, CO 80202

PHONE# (303) -623-4565 OPERATORS LICENSE NO. 04981

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-7-94 (date)

by Casey Morris (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	210'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4850'-2300'	50 sks cement @ 250'
50 sks cement @ 2300'	10 sks cement @ 40'
50 sks cement @ 1400'	10 sks in Mousehole
50 sks cement @ 700'	15 sks in Rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cholla Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1994

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public



15-171-20463-00-00

EMPHASIS OIL OPERATIONS
A Division of N-B Company, Inc.
P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Cholla Resources, Inc.
1641 California St., Ste. #400
Denver, Colorado 80202

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Fairleigh WELL #1-14

LOCATION: 150' C SW SW
Section 14-19S-34W
Scott County, Kansas

LOGGERS TOTAL DEPTH: 4853'

ROTARY TOTAL DEPTH: 4850'

COMMENCED: 2/24/94

CASING: 8-5/8" @ 210' w/155 sks cement

ELEVATION: 3048' K.B.

COMPLETED: 3/7/94

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	210'	Lansing-Kansas City	4170'
Shale	2110'	Marmaton	4416'
Anhydrite	2271'	Lime & Shale	4630'
Shale	2287'	R.T.D.	4850'
Lime & Shale	3650'		


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on March 8, 1994.

My commission expires: February 6, 1996.


GLENDA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-96


Glenda R. Tiffin, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 09 1994
CONSERVATION DIVISION
Wichita, Kansas