


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW&" or footage from lines Saline County. Sec. 10 Twp. 15 Rge. 2 W. (E) (W) SE SE SE
Lease Owner Melland Drilling Co.
Lease Name Burch Well No. I
Office Address P.O. Box 783 Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-27 1962
Application for plugging filed June 1964
Application for plugging approved June 1964
Plugging commenced June 24 1964
Plugging completed June 26 1964
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bert Stafford
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2792' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/8"		2456'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2792' to 2750'. Dumped 5 sx of cement. Mudded hole to 145'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1964
07-07-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2800 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. Art Lamb

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 th day of July 1964

My commission expires January 5, 1966 [Signature] Notary Public.

15-169-00454-00-00
WELL RECORD

LEASE: Burch

WELL NO. 1

ELEVATION: 1332 RB

LOCATION: SE SE SE
Sec. 10-15-2W

COMMENCED: 5/21/62

COMPLETED: 5/27/62

OPERATOR: Melland Drilling Co., Inc.

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, Kansas

CASING RECORD: 8 5/8" @ 130' / 100' ex
5 1/2" @ 2778' / 48' ex

FORMATION	LOG
clay & shale	75
shale & shells	100
anhydrite	260
lime	385
lime & shale	524
lime	725
shale	800
shale & shells	1420
lime & shale	1985
lime	2200
lime & shale	2560
shale & lime	2655
lime & shale	2780
RFD	2780

Sample Tops

Lansing 2143
Mississippian 2775

FORMATION	LOG
Drilled Deeper	
10/18/63	
lime	2790
dolomite	2792.5
T D	2792.5

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1964
07-07-1964
CONSERVATION DIVISION
Wichita, Kansas

MADE IN THE U.S.A.

LIQUID OIL ON 2W

CERTIFICATE

State of Kansas, County of McPherson, ss.

Donald J. Melland, do hereby certify that the above is a true and correct copy of the log of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,

this 24 day of June, 19 64.

My Commission expires: December 23, 1967

Frank B. Miller
Notary Public