

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline County, Sec. 11 Twp. 15 Rge. 2 (E) (W)

Location as "NE/CNW%SW%" or footage from lines 330- 330

Lease Owner George R. Hess & Larry Moore Ranch, Inc.

Lease Name James Johnson Well No. 1

Office Address Box 188 McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed October 26 19 54

Application for plugging filed October 26 19 54

Application for plugging approved October 29 19 54

Plugging commenced October 27 19 54

Plugging completed October 31 19 54

Reason for abandonment of well or producing formation Too much water & no oil

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Mississippian Depth to top 2808 Bottom 2818 Total Depth of Well 2818 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back to 2790'. Dumped 5 sacks of cement. Shot pipe off at 2677'.
Pulled pipe and mudded hole to 136'. Set rock bridge and dumped 15 sacks
of cement. Mudded hole to 36'. Set rock bridge and dumped 10 sacks of cement
at surface.

11-06-1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address RFD #4 McPherson, Kansas

STATE OF Kansas COUNTY OF McPherson, ss.

George R. Hess (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein and the log of the above-described well as filed and that the same are true and correct. So help me (God).

(Signature) George R. Hess

(Address)

SUBSCRIBED AND SWORN to before me this 3 day of November, 19 54

Carroll D. Winslow
Notary Public.

My commission expires January 17, 1957

PLUGGING
FILE 117 15 R2W
BOOK PAGE 23 LINK 21

COMPANY: George Hess & Larry Moore Ranch Inc.
 CONTRACTOR: Mallard Drilling Company
 FARM: *69122* Johnson #1
 LOCATION: SW SW SW Sec. 11-12-2W
 Saline County, Kansas
 COMMENCED: October 12, 1954
 COMPLETED: October 18, 1954

0	to	70	Shale and shells
70	to	131	Lime
131	to	495	Lime
495	to	1045	Lime
1045	to	1715	Shale and lime
1715	to	1880	Lime
1880	to	2060	Lime and shale
2060	to	2098	Shale
2098	to	2164	Brown lime
2164	to	2240	K.C. Lime
2240	to	2360	Lime
2360	to	2465	Lime
2465	to	2700	Lime and shale
2700	to	2790	Shale and lime
2790	to	2794	Shale
2794	to	2810	Sand
2810	to	2818	Lime
		2818	T.D. Notary

Set 131 feet of 8 5/8" surface pipe. Cemented with 90 sacks cement.

Set 4 1/2 inch at 2803. Cemented with 40 sacks cement.

TOPS: 2800 -- Mississippi

Measurements taken from R.D.B. R.D.B. 5 1/2 ft. from ground level.

C E R T I F I C A T E

I, C. G. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Johnson #1, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. G. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 20th day of October 1954.

Raymond Wright

My commission expires 12/4/56

PLUGGING
 FILE SEC 11-15-R2W
 BOOK PAGE 23 LINE 21

STATE OF KANSAS
 11-10-1954
 CONSERVATOR OF LANDS
 Wichita, Kansas