

15-169-00232-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 27 Twp. 15 Rge. 2 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 SE/4

Lease Owner George R. Hess

Lease Name Milliken Well No. 1

Office Address 505 N. Charles, McPherson, Kansas - 67460

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed Sept. 12, 1964

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced Sept. 12, 1964

Plugging completed Sept. 12, 1964

Reason for abandonment of well or producing formation Hole dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	110			
Anhydrite		110	130	8 5/8"	130'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 130 ft., and set plug with 20 sacks cement. Filled with mud to 40 ft. set top plug with 10 sacks cement and 2 sacks in rathole. Plugging completed at 9:00 P.M., September 12, 1964.

STATE CORPORATION COMMISSION

SEP 16 1964
09-16-1964
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas - 67460

STATE OF Kansas COUNTY OF McPherson ss.
George R. Hess (operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Hess
505 North Charles, McPherson, Ks 67460
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of September, 1964

My commission expires January 17, 1965
Carroll D. Winslow
Notary Public.



B-149-00232-00-00

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

September 14, 1964

COMPANY: GEORGE R. BESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MILLIKEN #1
 LOCATION: SE/4 SE/4 SW/4, Sec. 27-15-2W,
 Saline County, Kansas
 COMMENCED: September 7, 1964
 COMPLETED: September 12, 1964
 ELEVATION: 1349 F.S.

0	to	110	Shale
110	to	130	Anhydrite
130	to	185	Shale & Lime
185	to	770	Lime
770	to	1095	Lime & Shale
1095	to	1765	Shale & Lime
1765	to	1960	Lime & Shale
1960	to	2147	Shale & Lime
2147	to	2155	Kansas City Lime
2155	to	2510	Lime
2510	to	2710	Shale & Lime
2710	to	2828	Shale
2828	to	2875	Mississippi
		2875	T. D.

09-10-1964

Cut 12 1/4 in. hole to 130 ft. and run 135 ft. of 8 5/8 in. casing pipe and set on bottom at 130 ft. with 80 sacks cement. Plug down at 2:00 P.M., September 7, 1964. Cut 7 7/8 in. hole to 2875 ft. Hole dry and abandoned. Filled hole with mud to 130 ft. Set plug with 20 sacks. Filled with mud to 40 ft. set top plug with 10 sacks cement, and 2 sacks in rathole. Plugging completed at 9:00 P.M., September 12, 1964 by Gilbert Tomau, State Plugger.

TCPS: Kansas City - 2147' Mississippi - 2823'

Measurements taken from K. S.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Milliken #1, located on the SE/4 SE/4 SE/4 of Sec. 27-15-2W, Saline County, Kansas as reflected by the files of the Blackstone Drilling, Inc.

H. J. Plouffe

 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 14th day of September, 1964.

Rich W. Day

 RICH W. DAY - Notary Public

MY COMMISSION EXPIRES: December 10, 1965.