


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-169-00245-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 36 Twp. 15 Rge. 2 (X) X (W)
Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Mull Drilling Co., Inc.
Lease Name Wendt Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 14, 19 63
Application for plugging filed October 13, 19 63
Application for plugging approved 19
Plugging commenced October 13, 19 63
Plugging completed October 14, 19 63
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay-Shale		0	60			
Lime		60	130	8 8/8"	130'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 125 ft. Set plug with 1/2 sack hulls, and cemented with 20 sacks cement. Filled hole to 40 ft. with mud and 1/2 sack hulls on top. Cemented with 10 sacks cement. 2 sacks in rathole. Pluggin completed at 2:00 A.M., Oct. 14, 1963

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1963
10-18-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
J. A. Mull, Jr. (employer/owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1625 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of October 19 63

My commission expires 2/23/64

[Signature]
Notary Public.

10/18/63
9917-W

15-169-00245-00-00



Blackstone Drilling, Inc.

P. O. BOX 455 • PHONE CH 1-1250

McPHERSON • KANSAS

October 15, 1963

COMPANY: MULL DRILLING CO., INC.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: WENDT #1
LOCATION: NW/4 SW/4 SE/4, Sec. 36-15-2W,
Saline County, Kansas
COMMENCED: October 8, 1963
COMPLETED: October 14, 1963
ELEVATION: 1971 K. B.

0	to	80	Clay-Shale
80	to	130	Lime
130	to	480	Lime & Shale
480	to	680	Lime
680	to	995	Lime & Shale
995	to	1670	Shale & Lime
1670	to	1980	Lime & Shale
1980	to	2040	Sand
2040	to	2132	Shale & Lime
2132	to	2508	Lime
2508	to	2680	Lime & Shale
2680	to	2715	Shale & Lime
2715	to	2775	Lime & Shale
2775	to	2794	Mississippi
		2794	T. D.

RECEIVED
WICHITA STATE UNIVERSITY
OCT 16 1963
10-18-1963
CONSERVATION DIVISION
Wichita, Kansas

Cut 12 1/4 in. hole to 130 ft. and run 139 ft. of 8 5/8 in. casing and cemented pipe on bottom with 95 sacks cement and 3 sacks calcium chloride. Plug down at 5:30 P.M., October 8, 1963. Cut 7 7/8 in. hole to 2794 ft. and hole was dry and abandoned. Filled hole with mud to 125 ft. Set plug with 1/2 sack hulls on top and cemented with 20 sks. cement. Filled hole to 40 ft. with mud and 1/2 sks. hulls on top. cemented with 10 sacks cement. 2 sacks in rathole. Hole plugging completed at 2:00 A.M. October 14, 1963, by Gilbert J. Toman, State Plugger, Holyrood, Kansas.

TOPS: Heebner - 1917' Douglas - 1950' Brown Line - 2067'
 Lansing - 2132' Mississippi - 2779'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on the Wendt #1, located on Sec. 36-15S-2W, Saline County, Kansas as reflected by files of the Blackstone Drilling, Inc.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public, within and for McPherson County, Kansas this 15th day of October, 1963.

Ruth McVay - Notary Public

My Commission Expires: Dec. 18, 1965.