


STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-169-00242-00-00
WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Saline County. Sec. 34 Twp 16S Rge. 2 XXXXXX (W)
Location as "NE/CNW/SW" or footage from lines NW/4 NE/4 SW/4
Lease Owner Mull Drilling Co., Inc.
Lease Name Mayer Well No. 1
Office Address 1625 Wichita Plaza Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 15, 19.63
Application for plugging filed May 14, 19.63
Application for plugging approved 19.
Plugging commenced May 15, 19.63
Plugging completed May 15, 19.63
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	70			
Shale & Shells		70	132	8 5/8"	134.66'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 130 ft. with mud and set wood and rock
bridge to 125 ft. Cemented with 20 sacks cement through
drill pipe. Filled hole to 40 ft. with mud. Built
bridge of cottonseed hulls and 10 sacks cement. 2 sacks.
in rathole. Hole plugging completed at 9:00 A.M., May
15, 1963.

STATE CORPORATION COMMISSION
JUN 5 1963
06-05-1963
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. James Gear, Prod. Engr. (employee of owner) or (owner or agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature)

1625 Wichita Plaza Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1963

My commission expires October 16, 1965

Notary Public.



15-169-00242-00-00

Blackstone Drilling, Inc.P. O. BOX 455 • PHONE CH 1-1250
McPHERSON • KANSAS

May 15, 1963

COMPANY: MULL DRILLING CO., INC.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: MAYER # 1
LOCATION: NW NE SW, Sec. 34-16S-2W,
Saline County, Kansas
COMMENCED: May 3, 1963
COMPLETED: May 15, 1963
ELEVATION:

0	to	70	Shale
70	to	132	Shale & Shells
132	to	245	Shale & Shells
245	to	390	Anhydrite Lime
390	to	775	Lime
775	to	1150	Lime & Shale
1150	to	1880	Shale & Lime
1880	to	2110	Lime & Shale
2110	to	2260	Shale & Lime
2260	to	2685	Lime
2685	to	2800	Lime & Shale
2800	to	2890	Shale & Lime
2890	to	2902	Mississippi
		2902	T. D.

RECEIVED

JUN 5 1963
06-05-1963

Cut 12 1/4 in. hole to 132 ft. and run 134.66 ft. of 8 5/8 in. surface pipe and cemented with 100 sacks cement, on bottom at 132 ft. Plug down at 10:30 P.M., May 3, 1963. Cut 7 7/8 in. hole to 2902 ft. Hole dry and abandoned. Filled hole to 180 ft. and set wood and rock bridge to 125 ft. Cemented with 20 sacks cement through drill pipe. Filled hole to 40 ft. with mud. Built bridge of cottonseed hulls and 10 sacks cement. 2 sacks in rathole. Hole plugging completed at 9:00 A.M. May 15, 1963, by Gilbert Toman, State Plugger, Holyrood, Kansas.

TOPS: Brown - 2187' Kansas City - 2252' Mississippi - 2890'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc., do hereby certify that the above and foregoing is a true and correct copy of log on the Mayer #1 located on the Sec. 34-16S-2W, Saline County, Kansas as reflected by the files of the Blackstone Drilling, Inc.


H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public within and for McPherson County, Kansas this 15th May, 1963.


Ruth May - Notary Public

MY Commission Expires: December 18, 1965