

15-169-20225-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Saline SEC. 1 TWP. 16S RGE. 2W E/W
Location as in quarters or footage from lines:
400' FNL & 1320' FEL NE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Dale Curtis Reese
Lease Name Bowell Well No. 1
Office Address 415 E. Prescott, Salina, Kansas 67401
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed August 23, 1983
Application for plugging filed _____
Plugging commenced _____
Plugging completed August 23, 1983
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlin Unruh, Halstead, Ks.
Producing formation _____ Depth to top _____ bottom T.D.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Topsoil & Clay		0	10'	8 5/8"	10'	None
Shale & Lime		10'	211'	8 5/8"	201	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled with fluid & cemented at 270' with 50 sacks of cement. Cemented at 40'
with 10 sacks of cement, 10 sacks in rathole. Plugging completed at 10:15 A. M.
by State Plugger, Merlin Unruh, Halstead, Kansas.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Blackstone Drilling, Inc., P.O. Box 1184, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF Saline, ss.
Dale Curtis Reese (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Dale Curtis Reese
415 E. Prescott, Salina, Ks. 67401
(Address)

SUBSCRIBED AND SWORN TO before me this

30th day of August, 19 83




Barbara S. Bowman
STATE CORPORATION COMMISSION Notary Public.

My Commission expires: 7/5/87

AUG 31 1983
08-31-1983
CONSERVATION DIVISION
Wichita, Kansas

15-149-20325-00-00



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

August 23, 1983

COMPANY: DALE CURTIS KESSE
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: BOWELL #1
LOCATION: 400' FNL & 1320' FEL NE/4 Section 1-16-2W,
Saline County, Kansas
COMMENCED: August 17, 1983
COMPLETED: August 23, 1983
ELEVATION:

0	to	10	Top Soil & Clay
10	to	220	Shale & Lime
220	to	905	Lime & Shale
905	to	1300	Shale & Lime
1300	to	1645	Lime & Shale
1645	to	1970	Shale & Lime
1970	to	2550	Lime
2550	to	2680	Lime & Shale
2680	to	2735	Shale
2735	to	2745	Mississippi
			T. D.

Cut 12 1/2" hole to 211' and run 213' of 8 5/8" casing, cemented with 130 sacks of cement at 211'. Plug down 11:45 A. M., August 18, 1983. Filled hole with fluid & cemented at 270' with 50 sacks of cement. Cemented plug at 40' with 10 sacks of cement, 10 sacks in rathole. Hole dry and abandoned. Plugging completed by State Plugger, Marlin Unruh, Halstead, Kansas, AT 10:15 A. M., August 23, 1983.

TOPS: LANSING - 2093' MISSISSIPPI - 2735'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Bowell #1, located on the 400' FNL & 1320' FEL NE/4 Section 1-16-2W, Saline County, Kansas as is reflected by the files of Blackstone Drilling, Inc.

P. E. PLOUFFE, PRESIDENT

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 23rd day of August, 1983.

JOHNNIE L. SCHMIDT - NOTARY PUBLIC

JOHNNIE L. SCHMIDT
Notary Public, Kansas
My Comm. Expires 11/21/84

RECEIVED
STATE CORPORATION COMMISSION
08-31-1983
AUG 31 1983
CONSERVATION DIVISION
Wichita, Kansas