

15-169-00067-00-00


WELL PLUGGING RECORD

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Blitting Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Saline County. Sec. **35** Twp. **15** Rge. **3W** (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from linc. **SW NE SW**
 Lease Owner. ~~Miller~~ **F.S. Williams et al**
 Lease Name. **Miller** Well No. **1**
 Office Address. **Box 746 McPherson, Kansas**
 Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
 Date well completed **May 27th 1950** 19.....
 Application for plugging filed **June 1st, 1950** 19.....
 Application for plugging approved 19.....
 Plugging commenced **June 8th, 1950** 19.....
 Plugging completed **June 13th, 1950** 19.....
 Reason for abandonment of well or producing formation **Dry**



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production.....19.....
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Ruel Durkee, McPherson, Kansas**
 Producing formation **None** Depth to top..... Bottom..... Total Depth of Well **3376 1/2** Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	350	8 5/8"	350	0
		0	3349'	5 1/2"	3349'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Put six sacks of cement at 3346'. Shot pipe off at 2800' Pulled pipe and mudded hole to 150' Put in Rock bridge at 150' and dumped 15 sacks of cement Finished mudding hole and put five sacks cement at top of surface

06-22-1950


(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to **F.S. Williams Box 746, McPherson, Kansas**
 Address.....

STATE OF....., COUNTY OF....., ss.
 (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ruel Durkee*
 (Address) *agent*

SUBSCRIBED AND SWORN to before me this **22nd** day of **June**, 19**50**
Lillian W. Thurman
 Notary Public.

My commission expires **June 22 - 1952**



15-169-00067-00-00

COMPANY: F. S. Williams
 CONTRACTOR: Mallard Drilling Company
 FARM: Miller #1
 LOCATION: SW NE SW Sec. 35-15-3W
 Saline County, Kansas
 COMMENCED: May 10, 1950--rotary
 COMPLETED: May 19, 1950--rotary

0	to	240	Sand and shale
240	to	350	Lime
350	to	1150	Lime
1150	to	1820	Lime and shale
1820	to	2150	Lime
2150	to	2530	Lime
2530	to	2630	Lime
2630	to	2720	Lime and shale
2710	to	2850	Lime and shale
2850	to	2935	Chat
2935	to	2990	Chat
2990	to	3040	Chat
3040	to	3085	Chat
3085	to	3280	Lime and shale
3280	to	3358	Lime--T.D. Rotary
3358	to	3370	Viola lime
3370	to	3373	Show oil
3373	to	3376	Show water
		3376	T.D. cardwell

Set 350 feet of 8 5/8" surface pipe. Cemented with 200 sacks cement.

Set 5 1/2" pipe at 3349. Cemented with 50 sacks cement. 1 1/2" pipe.

Acidized with 1000 gallons acid. In 16 hours well filled up--100 feet oil and 700 feet water.

TOPS: Mississippi--2773 Viola --3356 Maquoketa--3355
Measurements taken from derrick floor.

DRY AND ABANDONED

JUN 15 1950
00-15-1950

C e r t i f i c a t e

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Miller #1, Sec. 35-15-3W, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 29th day of May 1950.

Spencer Wright

My commission expires 12/4/52

PLUGGING
FILE SEC. 25 T. 15 R. 36
BOOK PAGE 8 LINE 38

MAY 31 1950

15-169-00067-00-00

COMPANY: F. S. Williams
 CONTRACTOR: Mallard Drilling Company
 FARM: Miller #1
 LOCATION: SW NE SW Sec. 35-15-3W
 Saline County, Kansas
 COMMENCED: May 10, 1950--rotary
 COMPLETED: May 19, 1950--rotary

0	to	240	Sand and shale
240	to	350	Lime
350	to	1150	Lime
1150	to	1820	Lime and shale
1820	to	2150	Lime
2150	to	2530	Lime
2530	to	2630	Lime
2630	to	2710	Lime and shale
2710	to	2850	Lime and shale
2850	to	2935	Chat
2935	to	2990	Chat
2990	to	3040	Chat
3040	to	3085	Chat
3085	to	3280	Lime and shale
3280	to	3358	Lime--T.D. Rotary
3358	to	3370	Viola lime
3370	to	3373	Show oil
3373	to	3376 $\frac{1}{2}$	Show water
		3376 $\frac{1}{2}$	T.D. cardwell

Set 350 feet of 8 5/8" surface pipe. Cemented with 200 sacks cement.

Set 5 1/2" pipe at 3349. Cemented with 50 sacks cement. 14# pipe.

Acidized with 1000 gallons acid. In 16 hours well filled up--100 feet oil and 700 feet water.

TOPS: Mississippi--2773 Viola --3356 Maquakolo--3285
Measurements taken from derrick floor.

DRY AND ABANDONED

C e r t i f i c a t e

05-31-1950

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Miller #1, Sec. 35-15-3W, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 29th day of May 1950.

Raymond Wright

My commission expires 12/4/52

