

15-169-20117-00-00

STATE OF KANSAS

STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Saline County, Sec. 35 Twp. 15 Rge. 3 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines

NW NW SE
Lease Owner Range Oil Company, Inc.
Lease Name Bungler Well No. 1

Office Address 240 Page Court, 220 W. Douglas, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 3-6 19 81
Application for plugging filed 3-6 19 81
Application for plugging approved 3-6 19 81
Plugging commenced 3-6 19 81
Plugging completed 3-6 19 81

Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation Depth to top Bottom Total Depth of Well 3510
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	224	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Mud to 240', 1/2 sx hulls, Dry Hole Plug, 40 sx cement
Mud to 50', 1/2 sx hulls, Dry Hole Plug, 20 sx cement
Bridged rat hole w/empty sx, capped w/5 sx cement

RECEIVED
STATE CORPORATION COMMISSION
03-13-1981
MAR 13 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Range Drilling Company, Inc.
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gary L. Reed (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Gary L. Reed
240 Page Court, 220 W. Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1981

NORA S. DAVIDSON
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 12-1-87

Nora S. Davidson
Notary Public.

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 169 — 20,117-00-00
County Number

Operator
Range Oil Company, Inc.

Address
240 Page Court 220 West Douglas Wichita, Kansas 67202

Well No. 1 Lease Name Bunger

Footage Location
330 feet from (N) 35' line 330 feet from 35' (W) line of SE/4

Principal Contractor Range Drilling Company, Inc. Geologist S. Kreidler

Spud Date 2/21/81 Date Completed 3/6/81 Total Depth 3510 P.B.T.D.

MIRT 2/26/81


Directional Deviation Oil and/or Gas Purchaser

S. 35 T. 15 R. 3 NE
W

Loc. NW NW SE

County Saline

640 Acres
N



Locate well correctly

Elev.: Gr. 1278

DF 1282 KB 1285

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10	8 5/8	Used	224	Common	150	2% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbis.	MCF	bbis.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Oil and Gas Division
MAR 13 1981
CONSERVATION DIVISION
Wichita, Kansas
03-13-1981
C-10-1972

15-169-20117-00-00

Operator Range Oil Company, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: D & A	
Well No. 1	Lease Name Bunger		
S 35 T-15 R 3 ^{XK} W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH

C.G.

Exc	2144	-859	2144	-859
BKC	2500	-1215	2501	-1216
sk. ddb	2793	-1508	2793	-1505
Open	2881	-1596	2882	-1597
Cont.	3051	-1766	3058	-1773
Cont.	3205	-1920	3214	-1929
pp. ddb	3287	-2002	3301	-2016
1/2 lb	3337	-2052	3357	-2072
up sh	3415	-2130	3442	-2157
sd	3442	-2157	3442	-2157
ch	3474	-2189	3467	-2184
TD	3510	-2225	3511	-2226

2-26-81 MIRT

2-27-81 7:00 am D.l.g. @ 776

2-28-81 7:00 am D.l.g. @ 1900 3/4 1020 1 @ 1519

3-1-81 7:00 am D.l.g. 2640 3/4 @ 2010 @ 2596

3-2-82 7:00^{am} Fishing @ 3059

3-3-81 8:00 am PTD 3310 (-2025)
Starting DST # 3290-3310

3-4-81 6:00 am PTD 3375 (-2090) Run DST # 2 3365-3375
DST # 1 3290-3310 30-30-30-60 wk
blw Int. SI. Rec 5' mud NS. ISIP
575 FSIP 643 IFF 23-23 FFP 23-23
Temp 101°

3-5-81 6:00 am PTD 3485 (-2200) Run DST # 3 3476-3485
DST # 2 3365-3375 1 wk. Rec 23" Re. 10' mud
NS. ISIP 659 FSIP 666 IFF 15-23
FFP 23-23 Temp 104°

3-6-81 8:00 am RTD 3510 DST # 3 3476-3485
30-30-30-60 wk blw ddb 15" Rec
1' mud IFF 23-23 ISIP 30
FFP 23-23 FSIP 146 Temp 109°
Raw Petro Log. Preparing to
Plug & abandon

4 1/2" Csg. @ W/

Date

D & A 3-6-81

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="text-align: center;"><i>Robert G. Brooks</i> Signature</p> <p style="text-align: center;">V.P. Exploration Title</p> <p style="text-align: center;">March 9, 1981 Date</p>
---------------	--