

OR 15-169-00068-00-00

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline County. Sec. 35 Twp. 15 Rge. 3 (A) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. ~~SW $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$~~

Lease Owner. L. B. Jackson, Jr.

Lease Name. Oetting Well No. 1

Office Address. 503 McBirney Bldg., Tulsa, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole). Dry hole

Date well completed. April 15 19. 50

Application for plugging filed. May 8 19. 50

Application for plugging approved. May 10 19. 50

Plugging commenced. May 14 19. 50

Plugging completed. May 23 19. 50

Reason for abandonment of well or producing formation. Dry

If a producing well is abandoned, date of last production. 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkes

Producing formation. Viola Sand Depth to top. 3335 Bottom. 3368 Total Depth of Well. 3368 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City Lime		2135		8 5/8"	312'	
Mississippi Lime		2787		5 1/2"	3353'	
Kinderhook		3043				
Hunton Lime		3202				
Sylvan Shale		3218				
Maquoketa		3281				
White lime		3300				
Hard Lime (Viola ?)		3335				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Dumped 6 sacks of cement in bottom of the 5 1/2" pipe. Shot pipe off at 2768'. Pulled pipe and mudded hole to 150'. Put rock bridge at 150', and put 15 sacks of cement top. Finished mudding hole and put 5 sacks of cement at top of surface.

JUN 2 1950
06-02-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. L. B. Jackson, Jr.

Address. 503 McBirney Bldg.,

Tulsa, Oklahoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

M. F. Ashwill, Auditor (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. F. Ashwill


503 McBirney Bldg., Tulsa, Oklahoma.

(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of May, 19 50

Joe Christian Notary Public.

My commission expires.



15 169 00068-00-70

ROTARY DRILLERS LOG

D. B. Jackson Company
503 McBirney Bldg.
Tulsa, Oklahoma

H. D. Otting # 1

C SW/4 SE/4 NE/4
Sec. 35-15S-3W,
Saline County, Kansas

Commenced: April 1, 1950
Completed: April 15, 1950

Total Rotary Depth 3368 K.B.
K.B. 2.30' above D.F. -
Elevation 1277 D.F.
D.F. 2.50' above G.L.
K.B. 6.15' above top 8 5/8"
Hinderliter head

CASING RECORD

8 5/8" Surface 312' Cemented
200 sacks.
5 1/2" 14# J-55 3353' - 15'
off Rotary Bottom. Cemented
75 sacks.

CONTRACTOR: E. K. Carey, Contractor (Rig # 1) Box 620, McPherson, Kansas.

Figures Indicated Bottom of Formation "KB"

Rotary Table, Base & Cellar	9	Line and Shale	2160
Shale	90	Line	2220
Shale and Shells	115	Shale	2225
Shale	235	Line	2605
Line	255	Shale and Line	2700
Shale and Shells	275	Shale	2788
Line	312	Line and Shale	2835
Line and Shale	465	Line (Miss.)	3038
Shale and Line	680	Shale	3075
Line	790	Shale and Line	3205
Line and Shale	940	Line	3218
Shale and Shells	1140	Shale	3254
Shale and Line	1660	Shale and Line	3283
Line	1825	Line	3288
Line and Shale	1870	Shale and Line	3300
Line	1930	Line	3368 TD KB

Geologist on this well: Lucien Walker, Tulsa, Oklahoma

The above Drillers Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR

Herbert Rhoton

By Herbert Rhoton, Supt.

PLUGGING
FILE SEC 35 T 15 R 32 W
BOOK PAGE 4 LINE 43

05-23-1950