


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
111 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 29 Twp. 15 Rge. 3 W (E) (W)  
Location as "NE/CNW&SW&" or footage from lines. C NW SE  
Lease Owner Walter Nelson  
Lease Name Holmquist Well No. I  
Office Address 2072 Marc Salina, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed May 23 1965  
Application for plugging approved May 24 1965  
Plugging commenced May 24 1965  
Plugging completed May 31 1965  
Reason for abandonment of well or producing formation Went dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3440' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2861'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3440' to 3410'. Dumped 3 sx of cement. Mudded hole to 310'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1965  
C6-14-1965  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (matters or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2809mKing Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1965

My commission expires January 5, 1966  
[Signature] Notary Public.

15-169-19061-00-00

WELLSITE REPORT #1

Walter J. Nelson, et al.

Well Depth: 3440'  
Operator: Rex & Morris Drilling Co.  
Completed: 3-21-63  
Revised: 3-22-63

Location: Q. NW 22  
Section 19-178-27  
Sedona County, Kansas

Starting Record:  
3 5/8 @ 190' w/107 cement  
4 1/2 @ 2424' w/75 cement

FORMATION	DEPTH
Surface Hole	320
Lime and Shale	795
Shale and Lime	1730
Lime and Shale	1920
Shale and Lime	2100
Lime and Shale	2500
Shale and Lime	2875
Shale and Lime	3127
Lime and Shale	3428
Lime	3440

T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1965  
05-20-1965  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Nelson  
Paul D. Nelson, Geologist

STATE OF KANSAS  
COUNTY OF SEDONA, KS.

Subscribed and sworn to before me, a Notary Public, this 1st day of April, 1963.

Edward J. [Signature]  
Notary Public, State of Kansas

My commission expires August 6, 1964